



NOTES

1. ASPHALT TO BE PLACED AND SPREAD USING A MECHANICAL PAVER.
2. ASPHALT LAYERS (AFTER ROLLING) TO BE COMPACTED TO A MINIMUM 98% S.P.M.D.D.
3. IN THE EVENT OF UNSUITABLE SUB-GRADE MATERIAL, BASE IS TO BE OVER-EXCAVATED AND BACKFILLED WITH GRANULAR 'B' COMPACTED TO 98% S.P.M.D.D.
4. ALL BACKFILL TO BE COMPACTED IN LIFTS OF 100MM.
5. ENSURE POSITIVE DRAINAGE.
6. TAMP ALL EDGES TO A FIRM 45 DEGREE BEVEL.
7. ALL DIMENSIONS IN MILLIMETRES

3 METER MULTI-USE WALKWAY

REVISIONS				
NO.	COMMENTS	BY	DATE	APPROVED BY
1	RE-BRANDING	BC	05/02/2021	

CITY OF KAWARTHA LAKES ENGINEERING AND CORPORATE ASSETS			
<small>322 KENT ST. W. Box 9000, LINDSAY ON. K9V 4T7, (705) 324-9411</small>			
<small>DRAWN BY:</small>	<small>CHECKED BY:</small>	<small>DATE:</small>	
<small>BC</small>		<small>25/08/2020</small>	
<small>APPROVED BY:</small>		<small>DATE:</small>	



<small>CONTRACT NO:</small>	
<small>SCALE:</small>	1:20
<small>PAGE 1 OF</small>	
<small>DRAWING NO.</small>	CKL-413