



**NOTES**

1. ASPHALT TO BE PLACED AND SPREAD USING A MECHANICAL PAVER.
2. ASPHALT LAYERS (AFTER ROLLING) TO BE COMPACTED TO A MINIMUM 98% S.P.M.D.D.
3. IN THE EVENT OF UNSUITABLE SUB-GRADE MATERIAL, BASE IS TO BE OVER-EXCAVATED AND BACKFILLED WITH GRANULAR 'B' COMPACTED TO 98% S.P.M.D.D.
4. ALL BACKFILL TO BE COMPACTED IN LIFTS OF 100MM.
5. ENSURE POSITIVE DRAINAGE.
6. TAMP ALL EDGES TO A FIRM 45 DEGREE BEVEL.
7. ALL DIMENSIONS IN MILLIMETRES
8. BOLLARD SPACING IS TO BE CONSTRUCTED AS PER AODA REG. 413/12. 80.9.7

40MM HL-3  
50MM HL-8  
350MM GRAN 'A'

## 3 METRE MULTI-USE WALKWAY WITH BOLLARDS

REVISIONS				
NO.	COMMENTS	BY	DATE	APPROVED BY
1	RE-BRANDING	BC	10/02/2021	

CITY OF KAWARTHA LAKES  
ENGINEERING AND CORPORATE ASSETS

322 KENT ST. W. Box 9000, LINDSAY ON. K9V 4T7, (705) 324-9411

DRAWN BY: BC  
CHECKED BY: BC  
APPROVED BY:

DATE: 22/01/2021  
DATE:



CONTRACT NO:  
SCALE: 1:20  
PAGE 1 OF 1  
DRAWING NO.  
CKL-413 B